

PROJECT DETAILS

ACTIVITY– Installation of MDB, SMDB, DB, MCC& CB

Ref No:
Rev.No:0
Page 1 of 9

Serial No.	Sub-Activities	Hazards Identified (Generic & Task)	Risks Involved (People & Property)	Risk Rating			Control Measures	Residual Risk
				Severity	Probability	Initial Risk		
1.	Prepare work area	<ul style="list-style-type: none"> Unauthorized, untrained workers 	<ul style="list-style-type: none"> Cuts Abrasions 	2	A	L	<ul style="list-style-type: none"> TBT/DSTI to be conducted by the foreman/ safety officer prior to work commencement Task specific safety training to be provided Authorized personnel to undertake the job Daily safety inspection should be carried and eliminate the hazard. 	Low (ALARP)
2.	Manual Handling	<ul style="list-style-type: none"> Incorrect lifting of loads Sharp edges. Placing the object while fingers underneath. Slip/trip/fall (same level) Unsafe posture 	<ul style="list-style-type: none"> Back Injuries Cut to finger Strain Musculoskeletal Injuries 	3	C	M	<ul style="list-style-type: none"> Any lifting tasks shall be carried out by persons physically capable to do so No employee should be asked to carry loads above his capacity and in any case no load shall exceed 30kg per man. Mass of the load is more then to be equally shared Deploy enough number of personnel for lifting shall be appointed to the task depending upon the type of load to be lifted. Use easy mode of transport like trolley etc. Load not to be lifted above your shoulder Height Keep your fingers away from pinch point While placing the load Area to be illuminated with adequate lighting. Do not use pedestrian access for shifting materials, tools by hand. It should be used by through mechanical aids only. Proper personal protective equipments to be used while manual handling of materials and loads. 	Low (ALARP)

PROJECT DETAILS

ACTIVITY– Installation of MDB, SMDB, DB, MCC& CB

Ref No:
Rev.No:0
Page 2 of 9

Serial No.	Sub-Activities	Hazards Identified (Generic & Task)	Risks Involved (People & Property)	Risk Rating			Control Measures	Residual Risk
				Severity	Probability	Initial Risk		
3.	Traffic and road management	<ul style="list-style-type: none"> • Collision with vehicles • Poor identification • Unauthorized/ untrained Operator/ driver, banks men • Poor access for vehicle • Public movement 	<ul style="list-style-type: none"> • Fatality • Property damage • Fracture 	4	B	M	<ul style="list-style-type: none"> • Prior to start obtain all relevant approval from traffic department in connection to the use of road. • PTW to be approved from Consultant/Contractor prior to start the activity. • Trained and experienced operator/ driver and banks men to be appointed for the activity. • Restricted to unauthorized and public to enter the area. • Public vehicles and transport to be restricted to enter the work area and proper alternative way to be provided. • Warning sign boards to be placed and area to be well barricaded. • High visibility vest to be provided to flagman to increase visibility. • Flagman to be positioned to the areas wherever required. • Close supervision to be done at all times. 	Low (ALARP)
4.	Unloading and shifting panels and accessories with using crane and forklift	<ul style="list-style-type: none"> • Unauthorized, Untrained Workers • Failure of lifting tools & tackles. • Failure of lifting equipments. • Swinging of material • Damaged sling/wire rope or a chain sling • Poor maintenance of vehicle • Speedy operation • Over turn • Over load 	<ul style="list-style-type: none"> • Fatality • Fractures • Property damage • Injury to personal • Sprain and strain 	4	C	H	<ul style="list-style-type: none"> • Ensure the crane and forklift engaged is tested and having valid license and the operator has valid license and approved 3rd party certificate. • Engage trained and certified banks man & rigger. • Barricade and warning signs in to the area where lifting operation is carried out and restrict the entry. • Check list should be carried out to their vehicles by the operator prior to start any work • Use tagline for control of swing and alignment. • The crane must be stopped when the wind speed exceeds 38km/hr. 	M (ALARP)

PROJECT DETAILS

ACTIVITY– Installation of MDB, SMDB, DB, MCC& CB

Ref No:
Rev.No:0
Page 3 of 9

Serial No.	Sub-Activities	Hazards Identified (Generic & Task)	Risks Involved (People & Property)	Risk Rating			Control Measures	Residual Risk
				Severity	Probability	Initial Risk		
							<ul style="list-style-type: none"> •SWL should be clearly marked on the crane and should be check that is functioning. •The crane and trucks shall be periodically maintained and a periodical check has been done by the maintenance team. •Vehicle not to be left unattended at site (ie,to be switched off mode if required and keys removed) • SWL shall not be exceeded. • Load should be secured properly with the equipment. • Operators and rigger must wear high level of reflecting vest and adequate PPE (Shoe, helmet, leather gloves, goggles, over all) 	
5.	Stacking and Storing	<ul style="list-style-type: none"> • Unauthorized, untrained workers • Material fall from height • Improper stacking • Collapse of materials 	<ul style="list-style-type: none"> •Crush • Cut and abrasion • Damage to property 	3	B	M	<ul style="list-style-type: none"> • All materials shall be stored below 2 meter height. •If the material is too heavy, use hydraulic trolley to shift the material. • No storage of materials to be done in the work place, only required quantity to be taken for the job. • Personnel protective equipment must worn at all time during the activity. (Helmet, shoe, vest, overall, gloves, goggles, mask.) 	Low (ALARP)

PROJECT DETAILS

ACTIVITY– Installation of MDB, SMDB, DB, MCC& CB

Ref No:
Rev.No:0
Page 4 of 9

Serial No.	Sub-Activities	Hazards Identified (Generic & Task)	Risks Involved (People & Property)	Risk Rating			Control Measures	Residual Risk
				Severity	Probability	Initial Risk		
6.	Working with Hand tools.	<ul style="list-style-type: none"> • Slip, trip and fall • Damaged worn out hand tools • Flying objects 	<ul style="list-style-type: none"> • Fatigue • Trigger finger • Cuts and abrasions 	3	C	M	<ul style="list-style-type: none"> • Defective tools should not be issued or used to perform the task, to be checked by store keeper • Don't extend the spanner by using a pipe as an extension bar. • Never use a file as a lever • Never use a screw driver as a chisel • Don't work with oily or greased hands • Use eye/ face protection when there is flying materials hazard, wear gloves while required to protect the hands • Use right tools for the job 	Low (ALARP)
7.	Working with power tools (Grinder, Drill machine)	<ul style="list-style-type: none"> • Defective equipment • Electricity • Improper use of equipment • Poor maintenance • Untrained workers • Flying object • Noise and vibration • Fire • Dust 	<ul style="list-style-type: none"> • Hearing losses • Eye injury • Crushing • Back injury • Burns • Electrocutation • Ringing in the ear / Deafness 	3	C	M	<ul style="list-style-type: none"> • PTW to be applied and obtained prior to start, If spark producing activity is performed • Defective tools should not be issued or used to perform a task. • Monthly inspection should be carried out by the electrician and record to be kept at the store • All portable power tools should be fitted with adequate fuse protection either in the tool body or in its electrical plug. • The weight, size and type of tool should be selected to suit the job being carried out. • Don't lay the cables around the access way, it should be proper routing • Industrial distribution board and socket only to be used at site • No joints shall be made in electrical cable. 	M (ALARP)

PROJECT DETAILS

ACTIVITY– Installation of MDB, SMDB, DB, MCC& CB

Ref No:
Rev.No:0
Page 5 of 9

Serial No.	Sub-Activities	Hazards Identified (Generic & Task)	Risks Involved (People & Property)	Risk Rating			Control Measures	Residual Risk
				Severity	Probability	Initial Risk		
							<ul style="list-style-type: none"> • Trained and training card holding person only to operate suitable power tools. • Cable hangers shall be used to avoid the direct contact of power tools cable with the scaffolding members. • Electrical connection shall be routed through ELCB only. • Correct rate of ELCB should be used (Ex:- 30ma only acceptable) • Only those persons who have been adequately trained and experienced in the use of the tool should be allowed to use the same. Power tools shall have inspection sticker. • Tools should be stored and maintained in good working condition. • Appropriate PPE Should use (Goggles, Mask, Ear plug, Gloves, Shoe, Helmet, Overall, Vest) 	
8.	Working with ladder	<ul style="list-style-type: none"> • Person/ material falling from ladder • Over reaching • Over loading • Obstructions overhead/ adjacent to work location • Slippery or uneven surface 	<ul style="list-style-type: none"> • Sprain and strain • Fracture • Injury to the person 	3	C	M	<ul style="list-style-type: none"> • The ladder should extend minimum one meter from the top for safe movement • Heavy materials should not be carried • Do not erect in slippery, uneven surface • Should be set up with a 4 vertical to 1 horizontal slope(4:1) • Inspection and maintenance to be registered and recorded by the store keeper • Step ladder must fully open and lock and the devices to be as per manufacturer • Defective ladder should not be used and report it immediately • Do not work from the top of two rungs • Remember the 3 point contact 	Low (ALARP)

PROJECT DETAILS

ACTIVITY– Installation of MDB, SMDB, DB, MCC& CB

Ref No:
Rev.No:0
Page 6 of 9

Serial No.	Sub-Activities	Hazards Identified (Generic & Task)	Risks Involved (People & Property)	Risk Rating			Control Measures	Residual Risk
				Severity	Probability	Initial Risk		
							<ul style="list-style-type: none"> • Do not work in front of the door. If work is carried then locked the door or blocked off • Ladder to be used for short duration works only limited to 15 min. • Colour coded system to be implemented • Beware of overhead protrusions while climbing up the ladder. 	
9.	Working on mobile scaffold	<ul style="list-style-type: none"> • Uneven surface • Overhead structure and cable • Materials and worker fall from height • Untrained, unauthorized Workers • Collapse of scaffold 	<ul style="list-style-type: none"> • Sprain and strain • Fracture • Spinal cord damage • Musculoskeletal Injury • Fatality 	3	C	M	<ul style="list-style-type: none"> • Do not stack materials on to the scaffold • Visual inspection should carry before use • Out rigger fitted and breaks are locked on • Only trained scaffolders shall be involved in erection & dismantling activities. • No person to be on the scaffold while it is being moved • Scaffold only use in on level and surface area • Safety harness to be used above 2mtr height and anchored in above shoulder height at all time • Tagging system to be implemented (i.e., all safe scaffolds shall be provided with green tags and unsafe scaffolds with red tag) • Keep walkways free of obstacles, tools and Equipment • Never stand and sit on the hand rails • Mobile scaffold height should be restricted to 3.5 to 4 times the shortest base width, If height of scaffold exceeds raker support or it should be tied to the structure properly. 	Low (ALARP)

PROJECT DETAILS

ACTIVITY– Installation of MDB, SMDB, DB, MCC& CB

Ref No:
Rev.No:0
Page 7 of 9

Serial No.	Sub-Activities	Hazards Identified (Generic & Task)	Risks Involved (People & Property)	Risk Rating			Control Measures	Residual Risk
				Severity	Probability	Initial Risk		
10.	Working in near floor openings	<ul style="list-style-type: none"> •Material/equipment fall from height • Slip/trip/fall 	<ul style="list-style-type: none"> •Fatality •PropertyDamage • Fracture 	4	B	M	<ul style="list-style-type: none"> •PTW to be applied and obtained prior to start work • Authorized person to do the job. •Rigidbarrication and toe board to be provided to all external edges and where a fallcan occur. •Warning signboards to be provided in those areas. •PPE to be used at all times (Helmet, Shoes, Vest, Overall, Harness) 	Low (ALARP)
11.	Installation of panels, glanding, termination	<ul style="list-style-type: none"> • Untrained, unauthorized Workers • Material Fall • Sharp edges • Unsafe posture • Slip, trip and fall 	<ul style="list-style-type: none"> • Cut and abrasion • Back Injuries • Fatigue • Musculoskeletal Injuries 	3	C	M	<ul style="list-style-type: none"> • Authorized personnel to undertake the job •Work location shall be inspected by concerned supervisor / foreman. • Close supervision to be done at all times • Materials should not be kept in walkways and edge of the opening. • Proper communication to be maintained between the workers while doing the installation. • Maintain a good housekeeping policy to prevent from slip, trip, fall hazards. • PPE to be worn at all times(Gloves, goggles, mask, helmet, shoe, vest, overall) • Emergency procedure to be briefed to all personnel prior to start the activity. • Emergency evacuation plan shall be readily available according to site condition and briefed to the workforce prior to start. • Trained first aider, fire warden and emergency vehicle to be available at the site during the activity. 	Low (ALARP)

PROJECT DETAILS

ACTIVITY– Installation of MDB, SMDB, DB, MCC& CB

Ref No:
Rev.No:0
Page 8 of 9

Serial No.	Sub-Activities	Hazards Identified (Generic & Task)	Risks Involved (People & Property)	Risk Rating			Control Measures	Residual Risk
				Severity	Probability	Initial Risk		
12.	Working in hot weather	<ul style="list-style-type: none"> Heat Stress 	<ul style="list-style-type: none"> Dehydration Sunburn Skin Cancer 	2	B	M	<ul style="list-style-type: none"> Drink plenty of water Employees shall be trained about heat stress symptoms & first aid measures. Avoid highly physical tasks during the hottest part of the day Isotonic drinks to be provided 	Low (ALARP)
13.	While working at night shift	<ul style="list-style-type: none"> Poor illumination Slip/trip/fall 	<ul style="list-style-type: none"> Fatality Cuts 	3	B	M	<ul style="list-style-type: none"> Proper illumination to be provided light post to be secured from fall Proper cable management system to be Followed All materials to be staged in proper manner without obstacles 	Low (ALARP)
14.	Work Completion	<ul style="list-style-type: none"> Poor housekeeping Slip/trip/fall 	<ul style="list-style-type: none"> Fire 	2	A	L	<ul style="list-style-type: none"> General housekeeping, Remove all surface, unwanted waste materials from the building All necessary precautions will be adopted to prevent fire 	Low (ALARP)

PROJECT DETAILS

ACTIVITY– Installation of MDB, SMDB, DB, MCC& CB

Ref No:
Rev.No:0
Page 9 of 9

CONSULTANT RISK MATRIX

					Probability				
					A	B	C	D	E
Severity	People	Assets	Environment	Reputation	Improbable 1 in 100,000 Years	Remote 1 in 10,000 Years	Occasional 1 in 1000 years	Probable 1 in 100 years	Frequent 1 in 10 years
5-Catstrophic	Multiple fatalities or permanent total disabilities	Extensive damage	Massive effect	International impact	Medium Risk (ALARP)	High Risk			
4-Severe	Single fatalities or permanent total disabilities	Major damage	Major effect	National impact					
3-critical	Major injury or health effects	Local damage	Localised effect	Considerable impact					
2-Marginal	Minor injury or health effects	Minor damage	Minor effect	Minor impact					
1-Negligible	Slight injury or health effects	Slight Damage	Slight effect	Slight impact					
					Low Risk				

HIGH	3-E 4-C,D,E 5-B,C,D,E
MEDIUM	1-D,E 2-B,C,D,E 3-A,B,C,D 4-A,B 5-A
LOW	1-A,B,C 2A